

90 80 70 60 50 40 30 20 10 0

100

200

300


400

500

600

700

800



THIS DRAWING PREPARED IN CONJUNCTION WITH:

Revision			
Discipline	Drg No	Revisions	

KEY PLAN

## GENERAL NOTE:

- 1/ Generally all supply and return air ductwork are internally or externally insulated 50mm thermal as shown on plans and/or sections.
- 2/ Generally all acoustic insulation linings are 50mm with performance test Ref to plans and/or section for insulation tags.
- 3/ Allow for penetration flashing angles to all wall openings for one or both sides of opening as necessary subject to where visible & visible on one side one flashing, two sides two flashings.
- 4/ Allow for appropriate size A/P at all PD access for inspection if shown or not on drawing.
- 5/ Provide seismic restraint to all M/E/H services as necessary to project code requirement.
- 6/ Allow turning vanes to all short rad and/or 90° bends if shown or not.
- 7/ Allow all support brackets for "FAN, COND, etc" where shown or not.
- 8/ Allow pipe support and expansion as required. Refer to water schematic for location.

Issued	Rev	Description	Date	Drawn
CAD FILE NAME: ARCHITECT				

CLIENT

BUILDER

PROJECT

MECHANICAL SERVICES

TITLE  
**MECHANICAL SERVICES  
LEVEL 09 OVERVIEW**

APP PM DATE DSGN CHECK DATE

DRAWN DATE DRG CHECK DATE

PROJECT NUMBER SCALE@B1

1 : 150

N DRAWING NUMBER ISSUE