

FOR EXISTING DUCTWORK
PLEASE REFER TO DEMOLITION PLAN

FOR RELOCATION DUCTWORK
PLEASE REFER TO DEMOLITION PLAN

FOR EXISTING PIPEWORK
PLEASE REFER TO DEMOLITION PLAN

FOR RELOCATION PIPEWORK
PLEASE REFER TO DEMOLITION PLAN


THIS DRAWING PREPARED IN CONJUNCTION WITH:

Revision					
Discipline	Drp No	Revisions			

KEY PLAN

GENERAL NOTE:

- Generally all supply and return air ductwork are internally or externally insulated 50mm thermal as shown on plans and/or sections.
- Generally all acoustic insulation linings are 50mm with perforated foil. Ref to plans and/or section for insulation tags.
- Allow for penetration flashing angles to all wall openings for one or both sides of opening as necessary subject to where visible ie visible on one side one flashing, two sides two flashings.
- Allow for appropriate size A/P at all FD access for inspection if shown or not on drawing.
- Provide seismic restraint to all MECH services as necessary to project code requirement
- Allow turning vane's to all short rad and/or 90° bends if shown or not.
- Allow all support brackets for 'FAN, COND, etc' where shown or not.
- Allow pipe support and expansion as required. Refer to water schematic for location.
- All mechanical duct and piping services exposed to view will require painting in accordance with the project specification. This extends to accessible areas like risers and plantrooms's. Areas above ceilings or below floor cavities and any car park areas are excluded. Care is to be taken when placing duct identification stickers which prevent the specified finish. All attempts to place the stickers under soffit and out of view is to be undertaken. Stickers left exposed after installation are to be removed by the sheet metal contractor.



NOTE : LF - LOOSE FLANGES HAS TO BE SUPPLY WITH THE DUCT. DUCT SHOULD BE HAVE FIXED FLANGE AT ONE END ANOTHER HAVE RAW EDGE.

FOR PIPEING DETAILS PLEASE REFER TO DWG NO MES-TF-03-L01-021 & 022

ALL DIMENSIONS ARE TAKEN FROM ST RL 67980

Issued	Rev	Description	Date	Drawn

ARCHITECT

CLIENT

BUILDER

PROJECT

MECHANICAL SERVICES

TITLE
MECHANICAL SERVICES
LEVEL 01 SOUTH LAYOUT ZONE 1

APP/PM	DATE	DSGN CHECK	DATE
DRAWN	DATE	DRG CHECK	DATE
PROJECT NUMBER	SCALE@B1		
	150		
DRAWING NUMBER	ISSUE		

